San Antonio's Desalting Adventure

Kevin Morrison, P.G.

Project Coordinator – Water Resources

Multi-State Salinity Conference February 27, 2020





SAWS by the Numbers

One of the nation's largest municipally owned utilities

- 1.9 million population
- 939 square mile service area
- 977,000+ total customers
- 13,000 miles of pipe
- \$929 million budget
- \$2.6 billion 5-year capital program
- 1,700 employees






Regulating the Edwards Aquifer






Diversification and Long Term Water Supply Planning











Brackish Development Challenges

- Groundwater district regulations
- Public Opposition and Response
 - Concerns from public in adjacent county
 - Created a Science Committee to assist with education
- No aquifer data to design around









Brackish Program (Phase I)

General Information

- Program costs to date: \$201M
- Began producing water November 9, 2016



Brackish Program

Multi Phase Long Term Supply

- Ultimate build out of approx. 33,000 AFY
 - Phase I at II,200 AFY
- Source water from the Lower
 Wilcox formation
- Reverse osmosis treatment process
- Wells
 - 12 production (+2)
 - 2 injection





Membrane Pilot Testing

Pilot Testing Goals

- Receive TCEQ capacity rating and permit
- Test membranes from three manufacturers
- Test pre-treatment/post treatment options
 - "Open System" vs. "Closed System"
- Additional Investigations
 - Concentrate Pipe Loop Study
 - Air Leak Testing
 - System fouling trend and membrane autopsy




SAWS Membrane Pilot Test Unit



Brackish Program

- Project Components
 - 12 Production Wells
 - 2 Injection Wells
 - Conveyance Piping
 - Treatment Plant
 - Access Roads
 - Electrical System
 - SCADA System





Brackish Construction Challenges

County Boundaries




Concentrate Disposal







Reverse Osmosis Process Diagram





Post Treatment

- Calcite Contactors
- Degasifiers
- Chlorine Contact Chamber
- Source Water Bypass



Operational Challenges

- Turbidity Control
 - Well Operation
 - Plant Operational Strategy
- Membrane Fouling
 - Iron
 - Turbidity (fine sand & silt)



Additional Work

2019-2020

- Modeling of the aquifer conditions did not match actual performance
 - Lowered seven pumps
 - Drilling additional production well and retrofit test well





Summary

- New water resource developed
- Additional science developed for a new central Texas water supply
- Development of new resources will occasionally provide a few surprises
- Much of the success of the project was due to the assistance of the staff from plants at El Paso, Phoenix, and Florida







San Antonio's Desalting Adventure

Kevin Morrison, P.G.

Project Coordinator – Water Resources

Multi-State Salinity Conference February 27, 2020



